



Certificate of Compliance

This certificate is issued for the following:

Pipe Hanger Components for Automatic Sprinkler Systems

Model DB Clevis Hangers
Model LBC Beam Clamps
(see listing attached)

Prepared for:

Link Yapi Sanayi Ve Ticaret AS
Gebze Organize Sanayi Bolgesi 1000 Sokak No 1016
Cayirova, Kocaeli 41400
Turkey

Manufactured at:

Link Yapi Sanayi Ve Ticaret AS
Gebze Organize Sanayi Bolgesi 1000 Sokak No 1016
Cayirova, Kocaeli 41400
Turkey

FM Approvals Class: 1951

Approval Identification: PR450273

Approval Granted: July 3, 2019

To verify the availability of the Approved product, please refer to www.approvalguide.com

Said Approval is subject to satisfactory field performance, continuing Surveillance Audits, and strict conformity to the constructions as shown in the Approval Guide, an online resource of FM Approvals.

A handwritten signature in dark ink, appearing to read 'D. B. Fuller', is written over a horizontal line.

David Fuller
VP - Manager of Fire Protection
FM Approvals
1151 Boston-Providence Turnpike
Norwood, MA 02062 USA



Member of the FM Global Group



Certificate of Compliance

Automatic Sprinkler Systems Pipe Hangers Clevis Hangers

Product Designation	Hanger Rod Size, in. (mm)	Component Description	For Nominal Pipe Sizes, in.	Remarks
DB	3/8 (10)	Clevis Hanger	3/4, 1, 1 1/4, 1 1/2, 2, 2-1/2, 3, 4	a, b
DB	1/2 (12)	Clevis Hanger	5, 6, 8	a, b

Remarks:

- a) Available electrogalvanized
- b) Available hot dip galvanized

Automatic Sprinkler Systems Pipe Hangers C-Type Clamps

Product Designation	Hanger Rod Size, in. (mm)	Component Description	For Nominal Pipe Sizes, in.	Remarks
LBC	3/8 (10)	Beam Clamp	3/4 to 4	-
LBC	1/2 (12)	Beam Clamp	5 to 8	-



Member of the FM Global Group